

City of El Paso - City Plan Commission Staff Report

Case No: SUSU12-00042 Marin Cabral Subdivision

Application Type: Major Combination **CPC Hearing Date:** June 14, 2012

Staff Planner: Justin Bass, (915) 541-4930, bassjd@elpasotexas.gov
Location: West of Pendale Road and South of North Loop Drive

Acreage: 1.17 acres

Rep District: 7

Existing Use: Vacant

Existing Zoning: R-2/sc (Residential/ special contract) **Proposed Zoning:** R-2/sc (Residential/ special contract)

Nearest Park: Pueblo Viejo Park (0.50-mile)

Nearest School: Mission Valley Elementary School (0.94-mile)

Park Fees Required: \$2,740.00

Impact Fee Area: This property is not in an impact fee area and is not subject to

impact fees.

Property Owner:Omar I. Marin & Jaime CabralApplicant:CAD Consulting CompanyRepresentative:CAD Consulting Company

SURROUNDING ZONING AND LAND USE

North: R-F (Ranch-Farm)/ Single-family residential development

South: R-2/sc (Residential/ special contract)/ Single-family residential development

East: R-F (Ranch-Farm)/ Single-family residential development

West: R-2/sc (Residential/ special contract)/ Single-family residential development

THE PLAN FOR EL PASO DESIGNATION: G3 Post-War.

APPLICATION DESCRIPTION

The applicant proposes to subdivide the subject property into two residential lots. Access is proposed from Van Haselen Court. This subdivision is being reviewed under the current subdivision code.

Pendale Road, which abuts the side of Lot 1, is an existing collector on the Major Thoroughfare Plan and is currently substandard with 50-feet of right-of-way consisting of 22-ft of pavement and a total of 8-ft of parkway with no sidewalks. The subdivision code requires a 56-foot right-of-way consisting of 36-ft of pavement, and 5-ft parkways and 5-ft sidewalks on each side of the street. The applicant does propose to dedicate his proportionate share of right-of-way on Pendale

Road. Van Haselen Court, which the proposed lots front on to, is an existing local street and currently substandard with 60-ft of right-of-way consisting of 35-ft of pavement and 12.5-ft parkways on each side with no sidewalks. The subdivision code requires a 52-foot right-of-way consisting of 32-ft of pavement, 5-ft parkways, and 5-ft sidewalks on each side of the street.

The applicant requests to waive all right-of-way improvements on both streets. Per Section 19.10.050(A)1 of the subdivision code, the City Plan Commission may waive the requirement to dedicate and improve the substandard right-of-way if any of the following factors are met:

- a. Fifty per cent of the lots within a quarter mile of the proposed development have already been developed and the existing street improvements are in character with the neighborhood and have sufficient capacity to handle the increase in traffic to be generated by the proposed development; or,
- b. The plat is located within the City of El Paso's Extraterritorial Jurisdiction area, is not within the city's annexation path and written documentation from the County of El Paso has been received stating that the substandard road meets all County requirements and the County is willing to accept the dedication of the substandard road;
- c. For all plats located in the City of El Paso's Extraterritorial Jurisdiction area, written concurrence from the County of El Paso is required prior to the waiver of any dedication and/or improvements.

Staff agrees that factor (a) does apply in this situation.

DEVELOPMENT COORDINATING COMMITTEE

The Development Coordinating Committee recommends **approval** of the waiver for right-of-way improvements in accordance with Section 19.10.050(A)1 and **approval** of Marin Cabral Subdivision on a **Major Combination** basis, subject to the following conditions and requirements:

Planning Division Recommendation:

Approval with waiver. In this case, more than fifty percent (50%) of the lots within a quarter mile of the subject property are developed; and the abutting rights-of-way are both in character with the surrounding neighborhood and operate at intended capacity.

City Development Department - Land Development

We have reviewed subject plan and recommend **Approval**.

No Objection

Engineering Geotechnical Report shall be submitted along with the improvements plan. (comment has been addressed)

<u>Planning – Transportation</u>

Comment:

- 1. The existing cross-sections for Van Haselen Court and Pendale Road do not comply with Section 19.15.110 (Street Width and Design).
 - The proposed subdivision complies with the waiver requirements of Section 19.10.050.A.1.a (Roadway Participation) which allows for a waiver of the additional dedication and improvements required to bring Van Haselen Court and Pendale Road up to current development standards.

Notes:

- 1. A corner clip shall be required at the intersection of Pendale Road and Van Haselen Court.
- 2. All proposed paths of travel (accessible sidewalks, wheelchair access curb ramps and driveways) located within public rights-of-way shall be constructed in compliance with the current ADA/TAS regulations and City Design Standards for construction.

Parks and Recreation Department

We have reviewed <u>Marin Cabral Subdivision</u>, a minor plat map and offer Developer / Engineer the following comments:

Please note that this subdivision is composed of tow (2) "R-2/sc" Single-family residential dwelling lots and applicant is required to pay "Park fees" in the amount of \$2,740.00 based on the following calculations:

Fees calculated as follows:

2 (R-2/sc) Single-family dwelling lots @ 1,370.00 / dwelling = 2,740.00

Please allocate funds under Park Zone: MV-3

Parks with-in Park Zone: Marian Manor

Nearest Parks is located with-in Park Zone MV-4: **Pueblo Viejo**

If density /acreage is increased /decreased or the property zoning /use changes, then fees will be re-assessed based on applicable conditions.

El Paso Water Utilities

1. EPWU does not object to this request.

Water:

- 2. There is an existing eight (8) inch diameter water main that extends along Pendale Road fronting the eastern boundary of the subject property. This water main is available for service.
- 3. There is an existing six (6) inch diameter water main that extends along Van Haselen Court fronting the northern boundary of the subject property. This water main is available for service.
- 4. Previous water pressure readings from fire hydrant 1933 located at the east Right of Way line of Pendale Road at the intersection of Pendale Road and Van Haselen Court have yielded a static pressure of 92 pounds per square inch (psi), a residual pressure of 72 psi and a discharge of 1233 gallons per minute.
- 5. The owner should, for his own protection and at his own expense, install at the discharge side of each water meter a pressure regulator, strainer and relief valve, to be set for pressure as desired by the customer. The Lot owner shall be responsible for the operation and maintenance of the above-described water pressure regulating device.

Sanitary Sewer:

6. There is an existing thirty-six (36) inch diameter sanitary sewer interceptor that extends along Pendale Road fronting the eastern boundary of the subject property. No direct service connections are allowed to this interceptor as per the El Paso Water Utilities – Public Service Board Rules and Regulations.

- 7. There is an existing eight (8) inch diameter sanitary sewer main that extends along Pendale Road fronting the eastern boundary of the subject property. This sanitary sewer main dead-ends at a stub-out approximately 30 feet south of the northern boundary and extends north along Pendale Road. This main is available for service.
- 8. There is an existing eight (8) inch diameter sanitary sewer main that extends along Pendale Road fronting the eastern boundary of the subject property. This sanitary sewer main dead-ends at a manhole approximately 30 feet north of the southern boundary and extends south along Pendale Road. This main is available for service.
- 9. There are two (2) existing eight (8) inch diameter sanitary sewer mains that extend along Van Haselen Court fronting the northern boundary of the subject property. These sanitary sewer mains are available for service.

General:

10. Application for water and sewer services should be made 6 to 8 weeks prior to construction to ensure water for construction work. New service applications are available at 1154 Hawkins, 3rd Floor. A site plan, utility plan, grading and drainage plans, landscaping plan, the legal description of the property and a certificate-of-compliance are required at the time of application. Service will be provided in accordance with the current EPWU – PSB Rules and Regulations. The applicant is responsible for the costs of any necessary on-site and off-site extensions, relocations or adjustments of water lines and appurtenances.

EPWU Stormwater Division

- 1. Provide an approved drainage plan in accordance with Section 19.01.050 of the current city ordinance. The drainage plan shall be in compliance with the City of El Paso's Design Standards for Construction.
- 2. Revise the following on-site ponding note on the final plat. See on-site ponding note below. On-site Ponding Notes:
 - 7. On-site ponding areas and permanent elevation markers shall be constructed and inspected prior to building occupancy. Permanent Certificate of Occupancy, required to obtain utility services, will be issued only after the City of El Paso has performed the inspection.

El Paso Fire Department

No comments received.

911

No comments received.

Sun Metro

No comments received.

Central Appraisal District

No comments received.

El Paso Electric Company

No comments received.

Texas Gas Company

No comments received.

Ysleta Independent School District

No comments received.

Additional Requirements and General Comments:

- 1. Submit to the City Development Department Planning Division the following prior to recording of the subdivision.
 - a. Current certified tax certificate(s)
 - b. Current proof of ownership
 - c. Release of access document, if applicable
 - d. Set of restrictive covenants, if applicable
- 2. Every subdivision shall provide for postal delivery service. The subdivider shall coordinate the installation and construction with the United States Postal Service in determining the type of delivery service for the proposed subdivision. In all cases, the type and location of delivery service shall be subject to the approval of the United States Postal Service.

Attachments

- 1. Location map
- 2. Aerial map
- 3. Preliminary plat
- 4. Final plat
- 5. Application

ATTACHMENT 1




7

June 14, 2012

SUSU12-00042

MARIN CABRAL SUBDIVISION

ATTACHMENT 2



ATTACHMENT 4 BEING ALL OF TRACT 18A, BLOCK 12 YSLETA GRANT CITY OF EL PASO, EL PASO COUNTY TX. CONTAINING: 50,828.51 SQ, FT. OR 1.1668 ACRES ± CABRA 100 1 0 ii AND THE RESERVE THE PERSON OF THE PARTY AND THE THE PARTY BETWEEN A 164 IN COLUMN 2 IN COL LOCATION MAP: 1" = 600" **立是国际政治法**法 A TANK OF ANGELS OF FACES OF SACRES OF THE STATE OF STATE AND COMMAND SOUTH AND THE RATIO OF SOUTH PASS. IN CONTRACTOR WILL A SHARE OF SOME PASS ALARMO THE COMM SHARE TO RECOVERED IN THE COMMENT PROPERTY. Common of the case of the case of the Common A SE ANN SE SE SENSO DE SERVICE SE SENSO PRINCIPALI NOTA SE SENSO SE SENSO SE SENSO PER AN PRINCIPAL SENSO SENSO. SITE

ATTACHMENT 5



CITY PLAN COMMISSION APPLICATION FOR MAJOR SUBDIVISION COMBINATION APPROVAL

1	OF EL PASO	1
ENGIN	MAY 2.1 2012	DEPT
L P	NG & COMMUNICITION OF	3

	- v.		
SUBDIVISION NAME:	MALIN CABRAC	SUBDIVISION	
Legal description for the a	rea included on this plat (Tract, B) TRACT 18 VSCE	A BLOCK 12	
Property Land Uses:			
	ACRES SITES		ACRES SITE
Single-family	1-1668 2	Office	
Duplex		Street & Alley	
Apartment		Ponding & Drainage	
Mobile Home		Institutional	
P.U.D.		Other (specify below)	
Park			
School Commercial		Total No. Sites	
Industrial		Total (Gross) Acreage	1.1662
muustrai		Total (Gloss) Acreage	1-1000
What is suities assisted of	the above described property?	R-2 Proposed zon	
what is existing zoning of	the above described property?	Proposed zon	ning?
Will the residential sites, as	s proposed, permit development in	full compliance with all zoni	ng requirements of
existing residential zone(s)			8
1000 100 100 100 100 100 100 100 100 10			
What type of utility easeme	ents are proposed: Underground_	Overhead Comb	ination of Both
			ination of Both
What type of drainage is pr	roposed? (If applicable, list more		
What type of drainage is pr	roposed? (If applicable, list more	than one)	
What type of drainage is pr	roposed? (If applicable, list more	than one) SITE IDNBING	
What type of drainage is pro-	roposed? (If applicable, list more	than one) SITE IDNOING h development? Yes	No
What type of drainage is proved the special public improved is a modification or except.	roposed? (If applicable, list more	than one) SITE IDNOING h development? Yes on Ordinance proposed? Y.	No No No
What type of drainage is proved the special public improve is a modification or except if answer is "Yes", please of	roposed? (If applicable, list more ON ments proposed in connection wit ion of any portion of the Subdivisi explain the nature of the modificat	than one) SITE IDNOING h development? Yes on Ordinance proposed? Yes ion or exception	NoNo
What type of drainage is proved that type of drainage is "Yes", please of the type of drainage is proved that type of the type of t	roposed? (If applicable, list more	than one) SITE IDNOING h development? Yes on Ordinance proposed? Yes ion or exception	NoNo
What type of drainage is proved the special public improve its a modification or except if answer is "Yes", please of the second of the second is the second in the second is the second in the second	ments proposed in connection with ion of any portion of the Subdivision of the nature of the modification of special circumstances:	than one) SITE IDNOING h development? Yes on Ordinance proposed? Yes ion or exception	NoNo
What type of drainage is proved to the special public improved is a modification or except iff answer is "Yes", please of the second se	ments proposed in connection wit ion of any portion of the Subdivisi explain the nature of the modificat in of special circumstances:	than one) SITE IDDING h development? Yes ion Ordinance proposed? You not exception	No No No
What type of drainage is proved to the special public improved is a modification or except if answer is "Yes", please of the second second in the second second in the proposed subdivision when the proposed subdivision is proposed subdivision in the propo	ments proposed in connection with ion of any portion of the Subdivision of the nature of the modification of special circumstances:	than one) SITE IDDENG h development? Yes ion Ordinance proposed? You not exception No decide whether this application	No No No n is subject to the st

12.	Owner of record OMARIMARIN & JAINE C	ABRAL	449-8015
12.	(Name & Address)	(Zip)	(Phone)
13.	Developer		<u> </u>
	(Name & Addréss)	(Zip)	(Phone)
14.	Engineer CAD CONSULTING CO.		633-6422
	(Name & Address)	(Zip)	(Phone)
	CASHIER'S VALIDATION OWNER SIGNATURE:	Open Marin	TALMA CABARE
	FEE: \$2,088.00 REPRESENTATIVE:		

NOTE: SUBMITTAL OF AN APPLICATION DOES NOT CONSTITUTE ACCEPTANCE FOR PROCESSING UNTIL THE PLANNING DEPARTMENT REVIEWS THE APPLICATION FOR ACCURACY AND COMPLETENESS.